

GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

Mahatma Gandhi National Rural Employment Guarantee Scheme (MGNREGS – AP) and Other developmental schemes – Revision of Rural Standard Schedule of Rates (RSSR) – Orders – Issued.

PANCHAYAT RAJ AND RURAL DEVELOPMENT (RD.II) DEPARTMENT

G.O.Ms.No. 39

Dated:02.02.2011

Read the following:

1. G.O.Ms.No.195, PR&RD (RD.II) Dept., dated:29-06-2009
2. Notification of Ministry of Rural Development, GOI , dated:14-01-2011
3. GO. MS.No.32, PR&RD(RD II) Dept., dated:24.01.2011

ORDER :

In the reference 1st read above, Government issued orders on Rural Standard Schedule of Rates (RSSR) for unskilled manual task in works taken up under MGNREGS.

2. In the reference 2nd read above, Government of India have notified the minimum wage by revising the minimum wage for unskilled manual work taken up under MGNREGS from Rs.100/- to Rs.121/-.

3. Vide reference 3rd read above, the Government of Andhra Pradesh has revised the minimum wage for unskilled manual work taken up under MGNREGS from Rs. 100 to Rs.121/- in compliance of the reference cited above.

4. In view of the above and in partial modification of G.O.Ms.No.195 PR&RD (RD.II) Department dt.29.6.2009, Government orders revision of rates for manual tasks in RSSR, work wise, task wise rates are annexed to this order.

5. These orders shall come into effect immediately.

6. The copy of the GO is available on website www.rd.ap.gov.in

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

R.SUBRAHMANYAM
Principal Secretary to Government (R.D.)

To

The Commissioner, Rural Development, AP., Hyderabad

The Director (EGS) O/o the Commissioner (RD)

All the District Collectors and District Programme Coordinators, NREGS

All the Project Directors, DWMA & Addl. District Programme Coordinators, NREGS (communication through O/o CRD, Hyderabad)

All the Project Directors, DRDAs and Additional District Programme Coordinators, NREGS (communication through O/o CRD, Hyderabad)

All the Chief Executive Officers, ZPs and Additional District Programme Coordinators, NREGS. (communication through O/o CRD, Hyderabad)

The Project Officer, ITDA and Additional District Programme Coordinators of Eturu Nagaram (Warangal), Bhadrachalam (Khammam), Utnoor (Adilabad) and Parvathipuram (Vizianagarm), Srisaillam (Kurnool), Paderu (Visakhapatnam), Seethampeta (Srikakulam), Rampachodavaram (East Godavari) & KR Puram (West Godavari) (communication through O/o CRD, Hyderabad)

Copy to:

The Prl. Secretary, Finance (W&P) Dept., Govt. of A.P., Hyderabad.

The Prl. Secretary, PR., Govt. of A.P., Hyderabad.

The Prl. Secretary, Irrigation (I&CAD) of A.P., Hyderabad.

The Prl. Secretary, Tribal Welfare Dept., Govt. of A.P., Hyderabad.

The Secretary, R&B, Govt. of A.P., Hyderabad
The Prl. Secretary, EFS & T Dept., Govt. of A.P., Hyderabad
The Prl. Chief Conservator of Forests, Govt. of AP., Hyderabad
The Commissioner Disaster Management and EO Secy. to Govt.
The Commissioner, AMR-APARD, Rajendranagar, Hyderabad
The Commissioner, Tribal Welfare, Hyderabad
The Chairman and Members of Technical Committee.
The Engineer-in-Chief, Panchayat Raj Dept.
The Engineer-in-Chief, Irrigation Dept.
The Chief Engineer, Tribal Welfare
The Special Officers of NREGS–AP Districts (communication through O/o CRD, Hyd)
The Secretary, APREG Council, Hyderabad.
The Superintending Engineers of Panchayat Raj of NREGS –AP Districts.
(communication through O/o CRD, Hyderabad)
The Superintending Engineers of Irrigation Dept., of NREGS –AP Districts.
(communication through O/o CRD, Hyderabad)
PS to Prl. Secretary, RD, Govt. of A.P., Hyderabad
PR&RD (Genl.) Dept., (2 copies)
SF/SC.

//FORWARDED :: BY ORDER//

SECTION OFFICER

ANNEXURE to GO Ms.No. 39 , PR&RD (RD-II) (Department), dated :02 /02/2011

S. No.	Item of Work	Rates approved in RSSR 195, dt 26.9.2009 of PR&RD(RD-II)Dept. (in Rs.)	Rates now approved to ensure mini. Wage of Rs.121.0/-(in Rs.)	Remarks
1	Unskilled Labour	100/- per day	121.0/- per day	-
2	Bush clearance			
	i) Light shrub	2.5/sqm	3.02/sqm	-
	ii) Medium and Dense Shrub /besharam/rubber plants	3.15/sqm	3.81/sqm	-
	iii)Thin stemmed Julyflora (stem with periphery upto 150 cms)/ thick shrub	6.25/sqm	7.56/sqm	Thick shrub is relevant in tribal areas only
	iv)Thick stemmed Julyflora (stem with periphery more than 150 cms	9.35/Sqm	11.31/sqm	-
3	Removal of stumps			
	i) Removal of stumps of girth 30cms to 99cms(small stumps)	50/- per each	60.5/- per each	-
	ii) Removal of stumps of girth 100cms to 199cms(medium stumps)	62.5/- per each	75.62/- per each	-
	iii) Removal of stumps of girth 200cms to 299 cms(large stumps)	81.25/- per each	98.31/- per each	-
	iv) Removal of stumps of girth 300cms to 399 cms(large stumps)	106.25/- per each	128.56/- per each	-
	v) Removal of stumps of girth 400cms to 499 cms(large stumps)	137.5/- per each	166.37/- per each	-
	vi) Removal of stumps of girth 500cms to 599 cms(large stumps)	168.75/- per each	204.18/- per each	-
	vii) Removal of stumps of girth 600cms to 699 cms(large stumps)	212.50/-per each		Deleted

	viii) Removal of stumps of girth 700cms to 799 cms(large stumps)	275/-per each		Deleted
	ix) Removal of stumps of girth 800cms to 899 cms(large stumps)	343.75/-per each		Deleted
4	Earth work Excavation in Ordinary Soils with initial lead of 10 mt and initial lift of 2.0 mts.			
	Category-I			
	i) Roads, rock fill dams and desilting of tanks	58.75/ Cum	71.08/ Cum	-
	ii. a) Earth work excavation for contour bunding	43.75/ Cum	52.93/ Cum	-
	ii. b) Breaking of clods, tamping & sectioning for contour bunding	15.00 / Cum	18.15/ Cum	-
	Category-II			
	i) Farm ponds	100.00 / Cum	121.0/ Cum	-
	ii) Plantation pits			
	a) 0.9 mtsX0.9 mtsX0.9 mts size pit	85.00 / Cum	102.85/ Cum	-
	b) 0.6 mts X 0.6 mtsX 0.6 mts size of pit	85.00 / Cum	102.85/ Cum	-
	c) 0.45 mts X 0.45 mtsX 0.45 mts size of pit	75.00 / Cum	90.75/ Cum	-
	d) 0.3 mts X 0.3 mtsX 0.3 mts size of pit	75.00 / Cum	90.75/ Cum	-
	Category – III			
	All other works	81.15 / Cum	98.19/ Cum	-
5	Earthwork Excavation in Hard soils with initial lead of 10 mt and initial lift of 2.0 mts.			
	Category-I			
	i) Roads and rock fill dams	72.50/ Cum	87.72/ Cum	-
	ii) a) Earth work Excavation for contour Bunding	55/ Cum	66.55/ Cum	-
	ii) b) Breaking of clods, tamping and sectioning for contour bunding	17.50/ Cum	21.17/ Cum	-
	Category-II			
	i) Farm ponds	112.50/cum	136.12/ Cum	-
	ii) Plantation pits			
	a) 0.9 mtsX0.9 mtsX0.9 mts size pit	96.25/cum	116.46/ Cum	-

	b) 0.6 mts X 0.6 mtsX 0.6 mts size of pit	96.25/cum	116.46/ Cum	-
	c) 0.45 mts X 0.45 mtsX 0.45 mts size of pit	85.00/cum	102.85/ Cum	-
	d) 0.3 mts X 0.3 mtsX 0.3 mts size of pit	85.00/cum	102.85/ Cum	-
	Category -III			
	All other works	85.00/cum	102.85/ Cum	-
6	Earth work excavation in soils with mixture of gravel and soft disintegrated rock boulders (stoney earth) with initial lead of 10 mt and initial lift of 2.0 mts.			
	Category-I			
	i) Roads and rock fill dams	80/ Cum	96.8/ Cum	-
	ii) a) Earth work Excavation for contour Bunding	60/ Cum	72.60/ Cum	-
	ii) b) Breaking of clods, tamping and sectioning for contour bunding	20/ Cum	24.20/ Cum	-
	Category-II			
	i) Farm ponds	110 / cum	133.10/ Cum	-
	ii) Plantation pits			
	a) 0.9 mtsX0.9 mtsX0.9 mts size pit	100 / cum	121.0/ Cum	-
	b) 0.6 mts X 0.6 mtsX 0.6 mts size of pit	100/- cum	121.0/ Cum	-
	c) 0.45 mts X 0.45 mtsX 0.45 mts size of pit	90/- cum	108.9/ Cum	-
	d) 0.3 mts X 0.3 mtsX 0.3 mts size of pit	90/- cum	108.9/ Cum	-
	Category – III			
	All other works	90/- cum	108.9/ Cum	-
7	Earthwork excavation in soft disintegrated rock soils			
	Category – II			
	Farm ponds	125.00/cum	151.25/ Cum	-
	Category – III			
	All other works	112.50/cum	136.12/ Cum	-
8	STONE PITCING (Unskilled)			
	i) Farm Ponds – Labour charges for pitching only.	218.75/cum	264.68/ Cum	-

	ii) Minipercolation Tanks – Labour charges for ptiching only.	218.75/cum	264.68/ Cum	-
9	Rough Stone Dry Packing (Unskilled)			
	i) Rock Fill Dam, Stone Checks & Stone outlets – Labour charges for packing only.	125.00/cum	151.25/ Cum	-
	ii) Stone Terracing – Labour charges for packing only.	125.00/cum	151.25/ Cum	-
10	Benching with 0.45mx 0.45m size and 0.60mx0.30m size	15/-Rmt	18.15/ Cum	-
11	Carrying of earth / gravel by head loads – Leads & Lifts			
	i).For every additional Lead of 10 mts over and above initial lead of 10mt	12.50/cum	15.125/cum	-
	ii).For every additional lift of 1mt over and above initial lift of 2mts	12.50/cum	15.125/cum	-
12	Conveyance of silt , carted earth, stable casing soil and gravel excluding loading and unloading (In case of MI Tank work only), with Lead of			
	a) 0.25km	24/-cum		Deleted (issued rates already separately)
	b)0.50km	30/- cum		
	c)1 km	36/- cum		
	d) 2 km	42/- cum		
	e) 3 km	48/- cum		
	f) 4km	54/-cum		
	g) 5km	64/-cum		
	h) 6km	72/-cum		
	i) 7 km	80/-cum		
	j) 8 km	88/-cum		
	k) 9 km	96/-cum		
	l) 10 km	104/-cum		

13	Sharpening of crowbar	5/- per day	5/- per day	No change
14	Basket Replenishment charges	3/- per day	3/- per day	No change
15	Plantation works			
	Category : I			
	i) Survey and demarcation	16.25/- 100 Nos	19.66/- 100 Nos	-
	ii) Alignment and fixing of planting point with 0.45 meters length sticks	46.85/- 100 Nos.	56.68/- 100 Nos.	-
	iii) 0.45 meter sticks preparation and transportation at site.	25/- 100 Nos.	30.25 100 Nos.	-
	iv) a) Internal transportation of bag plants to planting points. (5"x9")	25/- 100 Nos.	30.25 100 Nos.	-
	iv) b) Internal transportation of Avenue Plantation. Tall plants	97/- 100 Nos.	117.37 100 Nos.	-
	v) Refilling of Pits and planting (mXmXm), staking stick			
	a) 0.30 X 0.30 X 0.30 Size pit	0.60/- each	0.72/- each	-
	b) 0.45 X 0.45 X 0.45 Size pit	1.85/- each	2.23/- each	-
	c) 0.60 X 0.60 X 0.60 Size pit	3.75/- each	4.53/- each	-
	d) 0.90 X 0.90 X 0.90 Size pit	5.60/- each	6.77/- each	-
	e) 1.00 X 1.00 X 1.00 Size pit	6.25/- each	7.56/- each	-
	Soil working and weeding			
	Category : I (1 M dia and 0.1 m Depth)			
	1) Avenue Plantation	6.25/- each	7.56/- each	-
	2) Horticulture	6.25/- each	7.56/- each	-
	Category : II (0.5 M dia and 0.1 m Depth)			
	i) Fore shore plantation	1.85/- each	2.23/- each	-
	ii) B.H.Afforstation	1.85/- each	2.23/- each	-
	iii) Bio Diesel Plantation & Block plantation	1.85/- each	2.23/- each	-
16	Causality Replacement for			
	i) Reopening of Pits for avenue, Horticulture & Blok Plantations.	6.35/- each	7.68/- each	-

	ii) Fore share plantation, Barren Hill Afforestation, Bio-Diesel	3.10/- each	3.75/- each	-
17	Watch & Ward and repair to Fence and soil working of each plant including pruning of branches for plantations raised in common property resource lands and lands of SC/ST/assignees.	100/- day	121.0/- day	-
18	Bio Fencing / Brush Wood Fencing for barren hill afforestation.			
	i) Nurseries, block plantation and fore shore plantation including collection, transportation and fixing at site	12.5/- Rmt	15.12/- Rmt	-
	ii) Avenue Plantation including collection, transportation and fixing at site (Size of 1 m dia and 1.5 m height)	47.30/- each	57.23/- each	-
	iii) Horticulture, for lands of SC-ST & Assignee lands only	1250/- acre	1512.5/- acre	-
	iv) Horticulture fencing 1 st year & 2 nd year maintenance SC-ST& Assignee lands only.	312.50/- acre	378.12/- acre	-
19	Deep Ploughing in			
	i) Fallow Land and Hard Gravel soils (Depth not less than 0.3 meters) using ploughing tractors	1000/- acre	1000/- acre	No change
	ii) fallow land in ordinary soils using ploughing tractor depth not less than 0.3 m	800/- acre	800/- acre	No change
	iii) Cattle cultivator(Double ploughing) in ordinary soils.	600/- acre	600/- acre	No change
20	Watering plants of block plantation from the sump constructed (where ever one sump is available per one acre)	1.60/- plant	1.93/- plant	-

21	Watering plants from hand pump/bore well/open well up to distance of 30 mt	2.25/- plant	2.72/- plant	-
22	Watering block plantation from the nearby sources i.e bore well open well or kunta beyond 30 mts distance.	2.80/- plant	3.38/- plant	-
23	Hire charges of tractor mounted water tanker for filling sump	300/- per one trip of 5000 ltrs capacity	300/- per one trip of 5000 ltrs capacity	No change
24	Construction of sump with 3 Nos of RCC Rings of 4 feet diameter , 1 foot height and 2 inch thickness prepared by using 2 Nos. of 4 mm dia MS rods with CM(1:5) and 4 mm dia metal chips for a sump with an inner volume of 37.68 cu.ft with 1066 litres capacity.	1200/- each sump	1452/- each sump	-
25	Labour charges for Spreading of silt unloaded by tractor in the field	12.15/- cum	14.70/- cum	-
26	Labour charges for breaking clods, trimming, sectioning and manual compaction using Dimmisa	15.00/-cum	15.00/-cum	No change
27	Removal of water hycinth upto 30cms thick	3.75/Sqm	3.75/Sqm	No change
28	Removal of water hycinth of more than 30cms thick	5.12/Sqm	5.12/Sqm	No change

Note : Rates of all materials and conveyance rates of materials other than silt, carted earth, stable casing soil and gravel shall be adopted from the relevant CSSR.

R.SUBRAHMANYAM
PRINCIPAL SECRETARY TO GOVERNMENT (RD)